



PROPOSED LUMINAIRE SCHEDULE

SYMBOL	LABEL	DESCRIPTION	MANUFACTURER	MODEL	WATTAGE	NOTE	QUANTITY	MOUNTING HEIGHT
☉	L-1	CANOPY, CEILING MOUNTED	WAC LIGHTING	FM-05SQ-930-BZ	12	BRONZE FINISH, 3000K COLOR TEMP.	1	9'-0"
▭	L-2	AREA LIGHT, WALL MOUNTED	LITHONIA	ARC2LED P4 30K	30	BRONZE FINISH, 3000K COLOR TEMP. MOTION SENSOR CONTROLLED	3	7'-0"
●	L-3	POST LIGHT	DESIGNERS FOUNTAIN	3133-BZ	5	BRONZE FINISH, 3000K COLOR TEMP. PHOTOCELL CONTROLLED	1	4'-0"
▭	L-4	WALL MOUNTED	WAC LIGHTING	DC-WS05-F830A-BZ	25	BRONZE FINISH, 3000K COLOR TEMP. MOTION SENSOR CONTROLLED	3	7'-0"


LIGHTING LEVELS:
 • OVERALL SITE MINIMUM = 0.0 FC
 • OVERALL SITE MAXIMUM = 28.9 FC
 • OVERALL SITE AVERAGE = 0.8 FC
 • PARKING AREA AVERAGE = 0.1 FC



**Inglese Architecture
+ Engineering**

632 Pompton Avenue
Cedar Grove, NJ 07009

1.201.438.0081
www.inglese-ae.com
info@inglese-ae.com



JOHN INGLESSE NJ A00846900
 JOAQUIN BOUZAS NJ G03999700
 ALEXANDER MERLUCCI NJ A01631300
 ANTHONY D'AGOSTA III NJ A02023700

THIS DOCUMENT IS THE EXCLUSIVE PROPERTY OF INGLESSE ARCHITECTURE + ENGINEERING. THE DOCUMENT AND THE INFORMATION IT CONTAINS MAY NOT BE REPRODUCED OR USED FOR OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT WAS PREPARED WITHOUT THE EXPLICIT CONSENT OF INGLESSE ARCHITECTURE + ENGINEERING.

CONSULTANTS:

**2475 LAMINGTON ROAD
BEDMINSTER TOWNSHIP
BLOCK: 27 LOT: 21 & 22**

SUBMISSIONS:
 VARIANCE PLAN 10.31.2023

REVISIONS:
 LIGHTING UPDATE 04.08.2024


IAE PROJECT NO. 23000

SHEET TITLE:
 LIGHTING SITE PLAN

SHEET:

C-1.50

1 LIGHTING SITE PLAN
 SCALE: 1" = 10'



2/2023/2000 - MODELING/SPACING - LAMINGTON ROAD - BEDMINSTER TOWNSHIP - APPROVALS - SHEETS - 150 - LIT - BMDIC - 150